Compliance Statement

Screened Class EA / Category 6A
ISO/IEC, EN & ANSI/TIA
Three Connector Permanent Link

Reichle & De-Massari AG
Binzstrasse 32,
CH-8620 Wetzikon, Switzerland

Compliance Statement No. 0473-3P-1241104

This type of Class EA / Category 6A Screened Three Connector Permanent Link has been tested by 3P Third Party Testing. The testing has shown compliance with the Class EA electrical performance requirements of edition 1.0 of ISO/IEC 11801-1:2017, edition 1.0 of ISO/IEC 11801-2:2017, CENELEC EN 50173-1:2018 and the Category 6A electrical performance requirements of ANSI/TIA-568.2-D:2018. The Compliance Statement is valid for the actually tested permanent link samples, consisting of the listed components. The tested permanent link is part of a 3P maintenance programme, with continuous verification of the electrical performance. The Compliance Statement is valid until 7 June 2026.

Cables:	*Horizontal Cable (15 – 75 m),*	*Screened Cat. 7*
		(P/N: see annex 1)
	Qualification Status:	*Manufacturer verified*
Conn. Hardware:	*Modular Jack,*	*Screened Connection Module Cat. 6A*
		(P/N: see annex 1)
	Qualification Status:	*Manufacturer verified*
Consolidation Cords:	*(10 m),*	*Screened Cat. 6A CP cord*
		(P/N: se annex 1)
	Qualification Status:	*Manufacturer verified*

Hoersholm, 7 August 2024

Peter Freiberg Kaas
Test Responsible

3P Third Party Testing ApS
Agern Alle 3
2970 Hørsholm
Denmark

www.3Ptest.dk

Hoersholm, 7 August 2024

Jens Rytter Petersen
General Manager

Annex 1

Compliance Statement No. 0473-3P-1241104

Part number	***Description***
R35061	Siamese Cable Cat. 7, S/FTP, 2x4P, 1000 MHz, LSFRZH, grey, Dca, 500 m
R833677	Installation Cable Cat. 7, S/FTP, 4P, 1000 MHz, LSFRZH, grey, Cca, 500 m
R35257	Installation Cable Cat. 7, S/FTP, 4P, 1000 MHz, LSZH, grey, Dca, 500 m
R35060	Installation Cable Cat. 7, S/FTP, 4P, 1000 MHz, LSFRZH, grey, Dca, 500 m
R35258	Siamese Cable Cat. 7, S/FTP, 2x4P, 1000 MHz, LSZH, grey, Dca, 500 m
R303013	Installation Cable Cat. 7, S/FTP, 4P, 1000 MHz, LSZH, grey, Dca, 1000 m
R309092	Installation Cable Cat. 7, S/FTP, 4P, 1000 MHz, LSFRZH, grey, Dca, 1000 m
R312595	Installation Cable Cat. 7, S/FTP, 4P, 1000 MHz, LSFRZH, orange, Dca, 1000 m
R317928	Installation Cable Cat. 7 S/FTP, 4P, 1000 MHz, LSFRZH AWG23 orange, 1000m
R809799	Installation Cable Cat. 7, S/FTP, 4P, 1000 MHz, LSFRZH, grey, Dca, 500 m
R809801	Installation Cable Cat. 7, S/FTP, 4P, 1000 MHz, LSFRZH, grey, Dca, 1000 m
R823885	Installation Cable, S/FTP, Class EA, PL 105m, 4P, AWG22, LSFRZH, grey, Dca, 500 m
R826304	Installation Cable Cat. 7, S/FTP, 4P, 1000 MHz, LSFRZH, orange, Dca, 500 m
R833664	Installation Cable Cat. 7, S/FTP, 4P, 1000 MHz, LSZH, orange, Dca, 500 m
R833680	Installation Cable Cat.7, S/FTP, 4P, 1200 MHz, AWG23, LSFRZH, grey, B2ca, 500m
R833686	Installation Cable Cat. 7, S/FTP, 4P, 1000 MHz, AWG23, LSFRZH, orange, Cca, 1000m
R837020	Installation Cable Cat. 7, S/FTP, 4P, 1000 MHz, LSFRZH, orange, B2ca, 1000 m
R837040	Siamese Cable Cat. 7, S/FTP, 2x4P, 1000 MHz, LSFRZH, grey, Cca, 500 m
R852294	Installation Cable Cat. 7, S/FTP, 4P, 1000 MHz, AWG23, LSFRZH, orange, Cca, 500 m
R854477	Installation Cable Cat. 7, S/FTP, 4P, 1000 MHz, LSFRZH, grey, Cca, 1000m
R885323	Installation Cable Cat.7, S/FTP 4P, 800MHz, LSZH, orange, Dca, 500 m
R885343	Installation Cable Cat. 7, S/FTP, 4P, 1000 MHz, AWG23, LSZH, grey, Dca, 500 m
R885344	Installation Cable Cat. 7, S/FTP, 4P, 1000 MHz, AWG23, LSFRZH, green, Cca, 500 m
R888892	Installation Cable Classic Cat. 7, S/FTP, 4P, 1000 MHz, AWG23, LSFRZH, orange, Cca,1000m
R892611	Installation Cable Cat.7, S/FTP 4P, 1000 MHz AWG23, LSFRZH, grey, Cca, 1000m
R896536	Installation Cable EA S/FTP, PL 105m, 4P 1000MHz AWG22 LSZH blue Cca 500m
R898183	Installation Cable Cat. 7, S/FTP, 4P, 1000 MHz, LSFRZH, grey, B2ca, 1000 m
R898187	Installation Cable Classic Cat. 7, S/FTP, 4P, 1000 MHz, AWG23, LSFRZH, grey, Cca, 1000m
R898246	Installation Cable Cat. 7, S/FTP, 4P, 1000 MHz, LSZH, grey, Cca, 500 m
R898247	Installation Cable Cat. 7, S/FTP, 4P, 1000 MHz, LSZH, grey, Cca, 1000 m
R910869	Installation Cable Classic Cat. 7, S/FTP, 4P, 1000 MHz, AWG23, LSFRZH, orange, Cca, 500m
R910871	Installation Cable Classic Cat. 7, S/FTP, 4P, 1000 MHz, AWG23, LSFRZH, grey, Cca, 500m
R320249	Installation Cable Cat. 7, F/FTP, 4P, 650 MHz, LSZH, grey, Dca, 500 m
R509856	Siamese Cable Cat. 7, F/FTP, 2x4P, 650 MHz, LSZH, grey, Dca, 500 m
R815143	Installation Cable Cat. 7, F/FTP, 4P, 650 MHz, LSFRZH, grey, Dca, 500 m
R833676	Installation Cable Cat. 7, F/FTP, 4P, 650 MHz, LSFRZH, grey, Cca, 500 m
R837039	Siamese Cable Cat. 7, F/FTP, 2x4P, 650 MHz, LSFRZH, grey, Cca, 500 m
R873753	Installation Cable Cat. 7, F/FTP, 4P, 650 MHz, LSZH, blue, Eca, 500 m
R873754	Installation Cable Cat. 7, F/FTP, 4P, 650 MHz, LSZH, green, Eca, 500 m
R886969	Installation Cable Cat. 7, F/FTP, 4P, 650 MHz, LSFRZH, green, Cca, 500 m
R313683	Industry Cable Cat. 7, S/FTP, 4P, 900 MHz, black, LSZH, Eca, 500 m
R313685	Industry Cable Cat. 7, S/FTP, 4P, 900 MHz, black, LSZH, Eca, 100 m
R823883	Industry Cable Cat. 7, S/FTP, 4P, 900 MHz, Eca, black, LSZH, 500 m
R832548	Industry Cable Cat. 7, S/FTP, 4P, 900 MHz, Eca, black, PE, 500 m

Hoersholm, 7 August 2024

Peter Freiberg Kaas
Test Responsible

3P Third Party Testing ApS
Agern Alle 3
2970 Hørsholm
Denmark

www.3Ptest.dk

Hoersholm, 7 August 2024

Jens Rytter Petersen
General Manager

Annex 1

Compliance Statement No. 0473-3P-1241104

Part number	***Description***
R509504	Module RJ45/s-C6A ISO-fr-10
R509505	Module RJ45/s-C6A-ISO-fr-100
R509506	Module RJ45/s-C6A-ISO-sn-10
R509507	Module RJ45/s-C6A-ISO-sn-100
R509509	Module RJ45/s-C6A ISO-ks-10
R510088	Module RJ45/s-C6A-ISO-sp-100
R511999	Module RJ45/s-C6A-ISO-sn-bk-24
R803927	Module RJ45/s-C6A ISO-sp-10
R808370	Module RJ45/s-C6A ISO-ad1
R813504	Module RJ45/s-C6A EL-fr-10
R813505	Module RJ45/s-C6A EL-fr-100
R813508	Module RJ45/s-C6A EL-sp-10
R813509	Module RJ45/s-C6A EL-sp-100
R813512	Module RJ45/s-C6A EL-ks-10
R813513	Module RJ45/s-C6A EL-ks-100
R813516	Module RJ45/s-C6A EL-sn-10
R813517	Module RJ45/s-C6A EL-sn-100
R813520	Module RJ45/s-C6A EL-ad-n1-10
R920679	Module RJ45/s-C6A-EL-4n-wt-AB-2226-20
R920680	Module RJ45/s-C6A-EL-4n-wt-AB-2226-100
R888230	Plug FM45 EL C6A s/u 22-26 IP20 m
R836543	Plug FM45 ELC6A s/u 22-26 IP20 ms
R886069	Plug FM45 ELC6A s/u 22-26 IP20 Am

Hoersholm, 7 August 2024

Peter Freiberg Kaas
Test Responsible

3P Third Party Testing ApS
Agern Alle 3
2970 Hørsholm
Denmark

www.3Ptest.dk

Hoersholm, 7 August 2024

Jens Rytter Petersen
General Manager