Compliance Statement

Screened Class EA / Category 6A
ISO/IEC, EN & ANSI/TIA
Three Connector Permanent Link

Reichle & De-Massari AG
Binzstrasse 32,
CH-8620 Wetzikon, Switzerland

Compliance Statement No. 0473-3P-1241105

This type of Class EA / Category 6A Screened Three Connector Permanent Link has been tested by 3P Third Party Testing. The testing has shown compliance with the Class EA electrical performance requirements of edition 1.0 of ISO/IEC 11801-1:2017, edition 1.0 of ISO/IEC 11801-2:2017, CENELEC EN 50173-1:2018 and the Category 6A electrical performance requirements of ANSI/TIA-568.2-D:2018. The Compliance Statement is valid for the actually tested permanent link samples, consisting of the listed components. The tested permanent link is part of a 3P maintenance programme, with continuous verification of the electrical performance. The Compliance Statement is valid until 7 June 2026.

Cables:	*Horizontal Cable (15 – 75 m),*	*Screened Cat. 7A (P/N: see annex 1)*
	Qualification Status:	*Manufacturer verified*
Conn. Hardware:	*Modular Jack,*	*Screened Connection Module Cat. 6A (P/N: see annex 1)*
	Qualification Status:	*Manufacturer verified*
Consolidation Cords:	*(10 m),*	*Screened Cat. 6A CP cord (P/N: see annex 1)*
	Qualification Status:	*Manufacturer verified*

Hoersholm, 7 August 2024

Peter Freiberg Kaas
Test Responsible

3P Third Party Testing ApS
Agern Alle 3
2970 Hørsholm
Denmark

www.3Ptest.dk

Hoersholm, 7 August 2024

Jens Rytter Petersen
General Manager

Annex 1

Compliance Statement No. 0473-3P-1241105

Part number	***Description***
R507032	Installation Cable Cat. 7A, S/FTP, 4P, 1500 MHz, AWG22, LSFRZH, grey, Dca, 500 m
R833681	Installation Cable Cat. 7A, S/FTP, 4P, 1200 MHz, AWG22, LSFRZH, grey, B2ca, 500 m
R837011	Installation Cable Cat. 7A, S/FTP, 4P, 1500 MHz, AWG22, LSFRZH, grey, Cca, 500 m
R885328	Installation Cable Cat.7A, S/FTP, 4P, 1200 MHz, AWG23, LSFRZH, grey, B2ca, 500 m
R107800	Installation Cable Cat.7A, S/FTP, 3P, 1500 MHz, AWG22, LSFRZG, grey, Dca, 500m
R306257	Installation Cable Cat. 7A, S/FTP, 4P, 1200 MHz, AWG22, LSFRZH, grey, Dca, 500 m
R306258	Installation Cable Cat. 7A, S/FTP, 4P, 1200 MHz, AWG22, LSFRZH, grey, Dca, 1000 m
R312594	Installation Cable Cat. 7A, S/FTP, 4P, 1300 MHz, AWG22, LSFRZH, orange, Dca, 1000 m
R319522	Installation Cable Cat. 7A, S/FTP, 4P, 1200 MHz, AWG23, LSFRZH, grey, Dca, 500 m
R508270	Installation Cable Cat. 7A, S/FTP, 4P, 1500 MHz, AWG22, Dca, LSFRZH, orange,1000 m
R510670	Siamese Cable Cat.7A, S/FTP, 4P,1200 MHz, AWG23, LSFRZH, grey, Dca, 500m
R510683	Installation Cable Cat.7A, S/FTP, 4P,1200 MHz, AWG23, LSFRZH, grey, Dca, 1000m
R809800	Installation Cable Cat. 7A, S/FTP, 4P, 1200 MHz, AWG23, LSZH, grey, Dca, 500 m
R809802	Installation Cable Cat. 7A, S/FTP, 4P, 1200 MHz, AWG23, LSZH, grey, Eca, 1000 m
R809803	Installation Cable Cat. 7A, S/FTP, 4P, 1300 MHz, AWG23, LSFRZH, orange, Dca, 1000 m
R810588	Siamese Cable Cat.7A, S/FTP, 2x4P, 1200 MHz, AWG22, LSFRZH, grey, B2ca, 500m
R823871	Installation Cable Cat. 7A, S/FTP, 4P, 1500 MHz, AWG22, LSFRZH, grey, Dca, 500 m
R826303	Installation Cable Cat. 7A, S/FTP, 4P, 1300 MHz, AWG22, LSFRZH, orange, Dca, 500m
R828595	Installation Cable Cat. 7A, S/FTP, 4P, 1200 MHz, AWG23, LSFRZH, grey, Cca, 500 m
R833678	Installation Cable Cat. 7A, S/FTP, 4P, 1200 MHz, AWG23, LSFRZH, grey, Cca, 500 m
R833679	Installation Cable Cat. 7A, S/FTP, 4P, 1200 MHz, AWG22, LSFRZH, grey, Cca, 500 m
R833683	Installation Cable Cat. 7A, S/FTP, 4P, 1500 MHz, AWG22, LSFRZH, orange, 1000 m
R833684	Installation Cable Cat. 7A, S/FTP, 4P, 1300 MHz, AWG22, LSFRZH, orange, Cca, 1000 m
R833685	Installation Cable Cat. 7A, S/FTP, 4P, 1200 MHz, AWG23, LSFRZH, orange, Cca, 500 m
R837019	Installation Cable Cat. 7A, S/FTP, 4P, 1300 MHz, AWG23, LSFRZH, orange, B2ca, 1000 m
R845862	Installation Cable Cat. 7A, S/FTP, 4P, 1300 MHz, AWG22, LSFRZH, orange, Cca, 1000 m
R845868	Installation Cable Cat. 7A, S/FTP, 4P, 1500 MHz, AWG22, LSFRZH, orange, Dca, 500 m
R855325	Installation Cabel Cat. 7A, S/FTP, 4P, 1300 MHz, AWG22, LSFRZH, grey, Dca, 1000 m
R855326	Installation Cable Cat. 7A, S/FTP, 4P, 1300 MHz, AWG22, LSFRZH, grey, Cca, 1000 m
R866527	Installation Cable Cat. 7A, S/FTP, 4P, 1000 MHz, LSFRZH, green, Cca, 1000m
R866542	Installation Cable Cat. 7A, S/FTP, 4P, 1200 MHz, AWG22, LSFRZH, grey, B2ca, 1000 m
R866543	Installation Cable Cat. 7A, S/FTP, 4P, 1200 MHz, AWG22, LSFRZH, grey, Cca, 1000 m
R866576	Installation Cable Cat. 7A, S/FTP, 4P, 1500 MHz, AWG22, LSFRZH, grey, Cca, 1000 m
R866577	Installation Cable Cat. 7A, S/FTP, 4P, 1500 MHz, AWG22, LSFRZH, grey, B2ca, 1000 m
R873752	Installation Cable Cat.7A, S/FTP, 4P, 1500 MHz, AWG22, LSFRZH, grey, Dca, 500m
R888893	Installation Cable Classic Cat. 7A, S/FTP, 4P, 1300 MHz, AWG22, LSFRZH, orange, Cca,1000 m
R892614	Installation Cable Classic Cat. 7A, S/FTP, 4P, 1200 MHz, AWG22, LSFRZH, grey, Cca, 1000 m
R896701	Installation Cable Classic Cat. 7A, S/FTP, 4P, 1500 MHz, AWG22, LSFRZH, orange, Cca,1000 m
R898186	Installation Cable Classic Cat. 7A, S/FTP, 4P, 1300 MHz, AWG22, LSFRZH, grey, Cca, 1000 m
R910872	Installation Cable Classic Cat. 7A, S/FTP, 4P, 1300 MHz, AWG22, LSFRZH, orange, Cca, 500 m
R910873	Installation Cable Classic Cat. 7A, S/FTP, 4P, 1300 MHz, AWG22, LSFRZH, grey, Cca, 500 m
R923082	Installation Cable Cat. 7A, S/FTP, 4P, 1200 MHz, AWG22, LSFRZH, orange, Cca, 1000 m
R837018	Installation Cable Cat.7A, S/FTP, 4P, 1500 MHz, AWG22, LSFRZH, orange, B2ca, 1000m
R852293	Installation Cable Cat.7A, S/FTP, 4P, 1300 MHz, AWG22, LSFRZH, orange, Cca, 500m

Hoersholm, 7 August 2024

Peter Freiberg Kaas
Test Responsible

3P Third Party Testing ApS
Agern Alle 3
2970 Hørsholm
Denmark

www.3Ptest.dk

Hoersholm, 7 August 2024

Jens Rytter Petersen
General Manager

Annex 1

Compliance Statement No. 0473-3P-1241105

Part number	***Description***
R509504	Module RJ45/s-C6A ISO-fr-10
R509505	Module RJ45/s-C6A-ISO-fr-100
R509506	Module RJ45/s-C6A-ISO-sn-10
R509507	Module RJ45/s-C6A-ISO-sn-100
R509509	Module RJ45/s-C6A ISO-ks-10
R510088	Module RJ45/s-C6A-ISO-sp-100
R511999	Module RJ45/s-C6A-ISO-sn-bk-24
R803927	Module RJ45/s-C6A ISO-sp-10
R808370	Module RJ45/s-C6A ISO-ad1
R813504	Module RJ45/s-C6A EL-fr-10
R813505	Module RJ45/s-C6A EL-fr-100
R813508	Module RJ45/s-C6A EL-sp-10
R813509	Module RJ45/s-C6A EL-sp-100
R813512	Module RJ45/s-C6A EL-ks-10
R813513	Module RJ45/s-C6A EL-ks-100
R813516	Module RJ45/s-C6A EL-sn-10
R813517	Module RJ45/s-C6A EL-sn-100
R813520	Module RJ45/s-C6A EL-ad-n1-10
R920679	Module RJ45/s-C6A-EL-4n-wt-AB-2226-20
R920680	Module RJ45/s-C6A-EL-4n-wt-AB-2226-100
R888230	Plug FM45 EL C6A s/u 22-26 IP20 m
R836543	Plug FM45 EL C6A s/u 22-26 IP20 ms
R886069	Plug FM45 ELC6A s/u 22-26 IP20 Am

Hoersholm, 7 August 2024

Peter Freiberg Kaas
Test Responsible

3P Third Party Testing ApS
Agern Alle 3
2970 Hørsholm
Denmark

www.3Ptest.dk

Hoersholm, 7 August 2024

Jens Rytter Petersen
General Manager