Compliance Statement

Screened Class D / Category 5e
ISO/IEC, EN & ANSI/TIA
Three Connector Permanent Link

Reichle & De-Massari AG
Binzstrasse 32,
CH-8620 Wetzikon, Switzerland

Compliance Statement No. 0473-3P-1241098

This type of Class D / Category 5e Screened Three Connector Permanent Link has been tested by 3P Third Party Testing. The testing has shown compliance with the Class D electrical performance requirements of edition 1.0 of ISO/IEC 11801-1:2017, edition 1.0 of ISO/IEC 11801-2:2017, CENELEC EN 50173-1:2018 and the Category 5e electrical performance requirements of ANSI/TIA-568.2-D:2018 incl. appendix 1 and 2. The Compliance Statement is valid for the actually tested permanent link samples, consisting of the listed components. The tested permanent link is part of a 3P maintenance programme, with continuous verification of the electrical performance. The Compliance Statement is valid until 7 June 2026.

Cables:	*Horizontal Cable (15 - 75m),*	*Screened Cat. 5e (P/N: see annex 1)*
	Qualification Status:	*Manufacturer verified*
Conn. Hardware:	*Modular Jack,*	*Screened Connection Module Cat. 5e (P/N: see annex 1)*
	Qualification Status:	*Manufacturer verified*
Consolidation Cords:	*(10 m),*	*Screened Cat.5e CP cord (P/N: see annex 1*
	Qualification Status:	*Manufacturer verified*

Hoersholm, 3 September 2024

Peter Freiberg Kaas
Test Responsible

3P Third Party Testing ApS
Agern Alle 3
2970 Hørsholm
Denmark

www.3Ptest.dk

Hoersholm, 3 September 2024

Jens Rytter Petersen
General Manager

Annex 1

Compliance Statement No. 0473-3P-1211286

Part number	***Description***
R35052	Installation Cable Cat. 5e, SF/UTP, 4P, 200 MHz, PVC,grey, Eca, 500 m
R35053	Installation Cable Cat. 5e, SF/UTP, 4P, 200 MHz, LSFRZH,grey, Dca, 500 m
R35054	Siamese Cable Cat. 5e, SF/UTP, 2x4P, 200 MHz, PVC,grey Eca, 500 m
R35055	Siamese Cable Cat. 5e, SF/UTP, 2x4P, 200 MHz, LSFRZH,grey,Dca,500 m
R302089	Installation Cable Cat. 5e, SF/UTP, 4P, 200 MHz, LSZH,grey, Eca, 500 m
R303286	Siamese Cable Cat. 5e, SF/UTP, 2x4P, 200 MHz, LSZH,grey, Eca, 500 m
R304365	Installation Cable Cat. 5e, SF/UTP, 4P, 200 MHz, LSFRZH,grey, Eca, 1000 m
R35048	Installation Cable Cat. 5e, F/UTP, 4P, 200 MHz, PVC,grey, Eca, 500 m
R35049	Installation Cable Cat. 5e, F/UTP, 4P, 200 MHz, LSZH,grey, Eca, 500 m
R35050	Siamese Cable Cat. 5e, F/UTP, 2x4P, 200 MHz, PVC,grey, Eca, 500 m
R35051	Siamese Cable Cat. 5e, F/UTP, 2x4P, 200 MHz, LSZH,grey, Eca, 500 m
R300316	Installation Cable Cat. 5e, F/UTP, 4P, 200 MHz, LSZH,grey, Eca, 305 m
R300317	Installation Cable Cat. 5e, F/UTP, 4P, 200 MHz, PVC,grey, Eca, 305 m
R302039	Installation Cable Cat. 5e, F/UTP, 4P, 200 MHz, LSFRZH,grey, Dca, 500 m
R845615	Installation Cable Cat. 5e, F/UTP, 4P, 200 MHz, LSZH, yellow, Eca, 500 m
R845846	Installation Cable Cat. 5e, F/UTP, 4P, 200 MHz, LSZH,red, Eca, 500 m
R845847	Installation Cable Cat. 5e, F/UTP, 4P, 200 MHz, LSZH ,blue, Eca, 500 m
R845848	Installation Cable Cat. 5e, F/UTP, 4P, 200 MHz, LSZH,green, Eca, 500 m
R35252	Module RJ45/s-C5e-DIN
R302780	Module RJ45/s-C5e-sn
R304325	Module RJ45/s-C5e-100
R305111	Module RJ45/s-C5e-sp
R308731	Module RJ45/s-C5e-sn-100
R814550	Module RJ45/s-C5e-sp-100
R925370	Module RJ45/s-C5e
R888230	Plug FM45 EL C6A s/u 22-26 IP20 m
R836543	Plug FM45 ELC6A s/u 22-26 IP20 ms
R886069	Plug FM45 ELC6A s/u 22-26 IP20 Am

Hoersholm, 3 September 2024

Peter Freiberg Kaas
Test Responsible

3P Third Party Testing ApS
Agern Alle 3
2970 Hørsholm
Denmark

www.3Ptest.dk

Hoersholm, 3 September 2024

Jens Rytter Petersen
General Manager