Compliance Statement

Unscreened Class EA / Category 6A
ISO/IEC, EN & ANSI/TIA
Three Connector Permanent Link

Reichle & De-Massari AG
Binzstrasse 32,
CH-8620 Wetzikon, Switzerland

Compliance Statement No. 0473-3P-1241101

This type of Class EA / Category 6A Unscreened Three Connector Permanent Link has been tested by 3P Third Party Testing. The testing has shown compliance with the Class EA electrical performance requirements of edition 1.0 of ISO/IEC 11801-1:2017, edition 1.0 of ISO/IEC 11801-2:2017, CENELEC EN 50173-1:2018 and the Category 6A electrical performance requirements of ANSI/TIA-568.2-D:2018 incl. appendix 1 and 2. The Compliance Statement is valid for the actually tested permanent link samples, consisting of the listed components. The tested permanent link is part of a 3P maintenance programme, with continuous verification of the electrical performance. The Compliance Statement is valid until 25 January 2027.

Cables:	*Horizontal Cable (15 – 75 m),*	*Unscreened Cat. 6A (P/N: see annex 1)*
	Qualification Status:	*Manufacturer verified*
Conn. Hardware:	*Modular Jack,*	*Unscreened Connection Module Cat. 6A (P/N: see annex 1)*
	Qualification Status:	*Manufacturer verified*
Consolidation Cords:	*(10 m)*	*Unscreened Cat. 6A CP cord (P/N: see annex 1)*
	Qualification Status:	*Manufacturer verified*

Hoersholm, 3 September 2024

Peter Freiberg Kaas
Test Responsible

3P Third Party Testing ApS
Agern Alle 3
2970 Hørsholm
Denmark

www.3Ptest.dk

Hoersholm, 3 September 2024

Jens Rytter Petersen
General Manager

Annex 1

Compliance Statement No. 0473-3P-1241101

Part number	***Description***
R804268	Installation Cable Cat. 6A, U/UTP, 4P, 650 MHz, PVC,grey, Ø 7.0mm, WARP, 500 m
R804269	Installation Cable Cat. 6A, U/UTP, 4P, 650 MHz, LSZH,grey, WARP, Dca, 500 m
R807391	Installation Cable Cat. 6A, U/UTP, 4P, 650 MHz, LSZH, blue, WARP, Eca, 1000 m
R809764	Installation Cable Cat. 6A, U/UTP, 4P, 650 MHz, LSFRZH,grey, Ø 7.0mm, WARP,Dca, 500 m
R812506	Installation Cable Cat. 6A, U/UTP, 4P, 650 MHz, LSZH,blue, WARP, 500m
R812508	Installation Cable Cat. 6A, U/UTP, 4P, 650 MHz, AWG 23, LSZH,orange, WARP, 500m
R812509	Installation Cable Cat. 6A, U/UTP, 4P, 650 MHz, AWG 23, LSZH,green, WARP, 500m
R814611	Installation Cable Cat.6A, U/UTP, 4P, 650MHz, LSZH, grey, WARP, Eca, 500 m
R815142	Installation Cable Cat. 6A, U/UTP, 4P, 650 MHz, LSZH,grey,WARP,Eca,305mm
R820276	Installation Cable Cat. 6A, U/UTP, 4P, 650 MHz, LSZH,grey, WARP, 500m
R820279	Installation Cable Cat. 6A, U/UTP, 4P, 650 MHz, CMP,grey,WARP,305m
R823248	Installation Cable Cat. 6A, U/UTP, 4P, 650 MHz, LSZH,blue, Ø 7.7mm, WARP,Eca, 305 m
R824373	Installation Cable Cat. 6A, U/UTP, 4P, 650 MHz,LSFRZH,grey,WARP,Dca, 500m
R828597	Installation Cable Cat. 6A, U/UTP, 4P, 650 MHz, LSZH,grey, Eca,WARP, 1000 m
R828598	Installation Cable Cat. 6A, U/UTP, 4P, 650 MHz, LSZH, green, WARP,Eca, 1000 m
R828599	Installation Cable Cat. 6A, U/UTP, 4P, 650 MHz, LSZH, yellow, WARP, 500 m
R837025	Installation Cable Cat. 6A, U/UTP, 4P, 650 MHz, LSZH, blue, WARP, Eca, 500 m
R837027	Installation Cable Cat. 6A, U/UTP, 4P, 650 MHz, LSZH, yellow, WARP,Eca; 500 m
R837028	Installation Cable Cat. 6A, U/UTP, 4P, 650 MHz, LSZH,green, Eca,WARP, 500 m
R852318	Installation Cable Cat.6A, U/UTP, 4P, 650MHz, AWG22, CMR, grey, 305m
R852319	Installation Cable Cat.6A, U/UTP, 4P, 650MHz, AWG22, CMP, grey, 305m
R854448	Installation Cabel Kat. 6A, U/UTP, 4P, 650 MHz, LSZH,grey, WARP, Cca, 500 m
R870401	Installation Cable Cat.6A, U/UTP, 4P, 650MHz, LSZH, blue, WARP, Eca, 500 m
R870402	Installation Cable Cat. 6A, U/UTP, 4P, 650 MHz, LSZH, dblue, WARP, Eca, 500 m
R870437	Installation Cable Cat. 6A, U/UTP, 4P, 650 MHz, LSZH,grey, WARP, Cca, 500m
R873747	Installation Cable Cat. 6A, U/UTP, 4P, 650 MHz, LSFRZH,grey, Ø 7.8mm, WARP,B2ca, 500 m
R873775	Installation Cable Cat. 6A, U/UTP, 4P, 650 MHz, LSZH,blue, WARP, 305m
R878977	Installation Cable Cat. 6A, U/UTP, 4P, 650 MHz, LSZH, blue, WARP, Dca, 305m
R892615	Installation Cable Cat. 6A, U/UTP, 4P, 650 MHz, LSZH, grey, WARP, Dca, 500m
R896534	Installation cable Cat. 6A, U/UTP, 4P, 650MHz, AWG23, LSZH grey, WARP, B2ca, 500m
ISO Modules	
R509500	Module RJ45/u-C6A-ISO-fr-10
R509501	Module RJ45/u-C6A-ISO-fr-100
R509502	Module RJ45/u-C6A-ISO-sn-10
R509503	Module RJ45/u-C6A-ISO-sn-100
R509508	Module RJ45/u-C6A ISO-ks-10
R510087	Module RJ45/u C6A-ISO-sp-100
R511998	Module RJ45/u-C6A ISO-sn-bk-24

Hoersholm, 3 September 2024

Peter Freiberg Kaas
Test Responsible

3P Third Party Testing ApS
Agern Alle 3
2970 Hørsholm
Denmark

www.3Ptest.dk

Hoersholm, 3 September 2024

Jens Rytter Petersen
General Manager

Annex 1

Compliance Statement No. 0473-3P-1241101

Part number	***Description***
EL Modules	
R813506	Module RJ45/u-C6A EL-fr-10
R813507	Module RJ45/u-C6A EL-fr-100
R813510	Module RJ45/u-C6A EL-sp-10
R813511	Module RJ45/u-C6A EL-sp-100
R813514	Module RJ45/u-C6A EL-ks-10
R813515	Module RJ45/u-C6A EL-ks-100
R813518	Module RJ45/u-C6A EL-sn-10
R813519	Module RJ45/u-C6A EL-sn-100
R813521	Module RJ45/u-C6A EL-ad-n1-10
Field mountable plugs	
R888230	Plug FM45 EL C6A s/u 22-26 IP20 m
R836543	Plug FM45 ELC6A s/u 22-26 IP20 ms
R886069	Plug FM45 ELC6A s/u 22-26 IP20 Am

Hoersholm, 3 September 2024

Peter Freiberg Kaas
Test Responsible

3P Third Party Testing ApS
Agern Alle 3
2970 Hørsholm
Denmark

www.3Ptest.dk

Hoersholm, 3 September 2024

Jens Rytter Petersen
General Manager