Compliance Statement

Unscreened Class E / Category 6
ISO/IEC, EN & ANSI/TIA
Three Connector Permanent Link

Reichle & De-Massari AG
Binzstrasse 32,
CH-8620 Wetzikon, Switzerland

Compliance Statement No. 0473-3P-1241099

This type of Class E / Category 6 Unscreened Three Connector Permanent Link has been tested by 3P Third Party Testing. The testing has shown compliance with the Class E electrical performance requirements of edition 1.0 of ISO/IEC 11801-1:2017, edition 1.0 of ISO/IEC 11801-2:2017, CENELEC EN 50173-1:2018 and the Category 6 electrical performance requirements of ANSI/TIA-568.2-D:2018. The Compliance Statement is valid for the actually tested permanent link samples, consisting of the listed components. The tested permanent link is part of a 3P maintenance programme, with continuous verification of the electrical performance. The Compliance Statement is valid until 7 June 2026.

Cables:	*Horizontal Cable (15 – 75 m),*	*Unscreened Cat. 6 (P/N: see annex 1)*
	Qualification Status:	*Manufacturer verified*
Conn. Hardware:	*Modular Jack,*	*Unscreened Connection Module Cat. 6 (P/N: see annex 1)*
	Qualification Status:	*Manufacturer verified*
Consolidation Cords:	*(10 m),*	*Unscreened Cat. 6 CP cord (P/N: see annex 1)*
	Qualification Status:	*Manufacturer verified*

Hoersholm, 7 August 2024

Peter Freiberg Kaas
Test Responsible

3P Third Party Testing ApS
Agern Alle 3
2970 Hørsholm
Denmark

www.3Ptest.dk

Hoersholm, 7 August 2024

Jens Rytter Petersen
General Manager

Annex 1

Compliance Statement No. 0473-3P-1241099

Part number	*Description*
R35056	Installation Cable Cat. 6, U/UTP, 4P, 450 MHz, PVC,grey, Eca, 500 m
R35057	Installation Cable Cat. 6, U/UTP, 4P, 450 MHz, LSZH,grey, Eca, 500 m
R305283	Installation Cable Cat. 6, U/UTP, 4P, 450 MHz, LSZH,grey, Eca, 1000 m
R317603	Installation Cable Cat. 6, U/UTP, 4P, 450 MHz, PVC,grey,305 m
R510085	Siamese Cable Cat. 6, U/UTP 2x4, 250MHz, LSZH, grey, Eca, 500 m
R510836	Installation Cable Cat.6, U/UTP, 4P, 450MHz, LSZH, violet, Eca, 500 m
R802920	Installation Cable Cat. 6, U/UTP, 4P, 450 MHz, LSZH,grey, Eca, 305 m
R804287	Installation Cable Cat. 6, U/UTP, 4P, 450 MHz, LSZH,orange, Eca, 305 m
R809346	Installation Cable Cat. 6, U/UTP, 4P, 450 MHz, LSZH,blue, Eca, 305 m
R809347	Installation Cable Cat. 6, U/UTP, 4P, 450 MHz, LSZH,green, Eca, 305 m
R809796	Installation Cable Cat. 6, U/UTP, 4P, 250 MHz, LSZH,grey,Dca, 305 m
R809797	Installation Cable Cat. 6, U/UTP, 4P, 250 MHz, PVC, grey, Eca,305 m
R809806	Installation Cable Cat. 6, U/UTP, 4P, 450 MHz, PVC, blue, Eca, 500 m
R813808	Installation Cable Cat. 6, U/UTP, 4P, 250 MHz, LSZH, grey, 500 m
R814603	Installation Cable Cat. 6, U/UTP, 4P, 250 MHz, LSZH, grey, 1000 m
R820801	Installation Cable Cat. 6, U/UTP, 4P, 250 MHz, LSZH, grey, 905 m
R821301	Installation Cable Cat. 6, U/UTP, 4P, 450 MHz, LSFRZH,grey, Dca, 1000 m
R837037	Installation Cable Cat. 6, U/UTP, 4P, 450 MHz, LSZH,grey, Cca, 500 m
R842467	Installation Cable Cat. 6, U/UTP, 4P, 250 MHz, LSZH,grey, Cca, 500 m
R842468	Installation Cable Cat. 6, U/UTP, 4P, 450 MHz, LSZH,grey, Dca, 500 m
R845613	Installation Cable Cat. 6, U/UTP, 4P, 250 MHz, LSZH, grey,305 m
R845864	Installation Cable Cat. 6, U/UTP, 4P, 450 MHz, LSZH,grey, B2ca, 500 m
R852286	Installation Cable Cat. 6, U/UTP, 4P, 250 MHz, LSZH,grey, B2ca,305m,ETR
R853222	Installation Cable Cat. 6, U/UTP, 4P, 250 MHz,LSZH, grey,500 m
R854455	Installation Cable Cat. 6, U/UTP, 4P, 250 MHz, LSZH,grey, B2ca, 500 m, ETR
R939882	Installation Cable Cat. 6, U/UTP, 4P, 250 MHz, LSZH, red, B2ca, 500 m, ETR
R939929	Installation Cable Cat. 6, U/UTP, 4P, 250 MHz, LSZH, green, B2ca, 500 m, ETR
R939937	Installation Cable Cat. 6, U/UTP, 4P, 250 MHz, LSZH, violet, B2ca, 500 m, ETR
R859084	Installation Cable Cat. 6, U/UTP, 4P, 450 MHz, LSFRZH,grey, B2ca, 500 m
R861314	Installation Cable Cat. 6, U/UTP, 4P, 450 MHz, LSFRZH,grey, Dca, 500 m
R883518	Installation Cable Cat. 6, U/UTP, 4P, 450 MHz, LSZH,red, Eca, 500 m
R898154	Installation Cable Cat. 6, U/UTP, 4P, 250 MHz, LSZH,grey,Cca, 305m
R302373	Module RJ45/u-C6
R304328	Module RJ45/u-C6-100
R304374	Module RJ45/u-C6-sn
R305114	Module RJ45/u-C6-sp
R308734	Module RJ45/u-C6-sn-100
R512369	Module RJ45/u-C6-sn-bk-24
R810597	Module RJ45/u-C6 Eco
R810598	Module RJ45/u-C6 Eco-sn
R813810	Module RJ45/u-C6-ks-10
R814553	Module RJ45/u-C6-sp-100
R823889	Module RJ45/u-C6 Eco-ks
R823890	Module RJ45/u-C6 Eco-ks-24

Hoersholm, 7 August 2024

Peter Freiberg Kaas
Test Responsible

3P Third Party Testing ApS
Agern Alle 3
2970 Hørsholm
Denmark

www.3Ptest.dk

Hoersholm, 7 August 2024

Jens Rytter Petersen
General Manager

Annex 1

Compliance Statement No. 0473-3P-1241099

Part number	***Description***
R888230	Plug FM45 EL C6A s/u 22-26 IP20 m
R836543	Plug FM45 ELC6A s/u 22-26 IP20 ms
R886069	Plug FM45 ELC6A s/u 22-26 IP20 Am

Hoersholm, 7 August 2024

Peter Freiberg Kaas
Test Responsible

3P Third Party Testing ApS
Agern Alle 3
2970 Hørsholm
Denmark

www.3Ptest.dk

Hoersholm, 7 August 2024

Jens Rytter Petersen
General Manager